


NOTES:

1. PORTLAND CEMENT CONCRETE (PCC) SHALL BE A MINIMUM 4000 PSI COMPRESSIVE STRENGTH @ 28 DAYS WITH MINIMUM 6.25 SACKS OF TYPE II CEMENT (588 LBS) PER CUBIC YARD OF CONCRETE, A MAXIMUM WATER/CEMENT RATIO OF 0.45, 4.5–7.5% AIR ENTRAINMENT, AND SLUMP SHALL RANGE FROM A MINIMUM OF 1" TO A MAXIMUM OF 4". IF COLORED CONCRETE, CONCRETE SHALL BE A MINIMUM OF 7 SACKS OF TYPE II CEMENT (658 LBS) PER CUBIC YARD OF CONCRETE WITH A MINIMUM 4000 PSI COMPRESSIVE STRENGTH @ 28 DAYS AND 4.5–7.5% AIR ENTRAINMENT.
2. ALL MATERIALS SHALL CONFORM TO THE LATEST EDITION OF THE STANDARD SPECIFICATIONS FOR PUBLIC WORKS CONSTRUCTION (SSPWC), EXCEPT WHERE SPECIFIED IN WASHOE COUNTY DETAILS AND SPECIFICATIONS.
3. ALL CRACK CONTROL JOINTS SHALL BE 7 FEET MAXIMUM.
4. AGGREGATE BASE SHALL BE TYPE 2 CLASS B COMPACTED TO 95% MINIMUM RELATIVE COMPACTION PER ASTM D-1557.
5. EVAPORATION REDUCERS SHALL BE APPLIED IMMEDIATELY AFTER INITIAL CURING.
6. FINISHING AND CURING SHALL CONFORM TO REQUIREMENTS OF THE LATEST EDITION OF THE SSPWC.
7. TESTING SHALL CONFORM TO REQUIREMENTS OF THE LATEST EDITION OF THE SSPWC.
8. CURB REMOVAL SHALL BE TO NEAT SAWCUT LINES.
9. NO EQUIPMENT SHALL BE PERMITTED ADJACENT TO OR ACROSS THE CURB AND SIDEWALK UNTIL THE FOURTH DAY FOLLOWING PLACEMENT OF THE CONCRETE, OR UNTIL THE CONCRETE HAS REACHED A MINIMUM COMPRESSIVE STRENGTH OF 3,000 PSI.
10. REINFORCING SHALL CONSIST OF COLLATED, FIBRILLATED, POLYPROPYLENE FIBERS AS MANUFACTURED BY FIBERMESH, OR APPROVED EQUAL, AND SHALL BE ADDED AT A RATE OF 1.5 LBS PER CUBIC YARD OF CONCRETE.
11. CURB AND GUTTER AND SIDEWALK SUBGRADE SHALL BE COMPACTED TO 90% MINIMUM RELATIVE COMPACTION. IF EXPANSIVE OR UNSUITABLE MATERIALS ARE ENCOUNTERED AT SUBGRADE ELEVATION, THE SOILS SHALL BE OVER-EXCAVATED TO CONFORM TO THE SOILS REPORT OR REQUIREMENTS OF WASHOE COUNTY. THE SUBGRADE SHALL BE INSPECTED AND APPROVED BY WASHOE COUNTY PRIOR TO PLACEMENT OF AGGREGATE BASE.
12. SEE ROADWAY SECTIONS FOR SIDEWALK WIDTHS.
13. ALL DRIVEWAY APRONS SHALL CONFORM TO DRAWING Nos. W-142A, W-142B, W-142C, W-142D, W-142E AND W-141.
14. CURB AND GUTTER AND SIDEWALK SHALL RECEIVE A LIGHT BROOM FINISH.

DATE	REVISIONS		STANDARD DETAILS FOR PUBLIC WORKS CONSTRUCTION	
			MONOLITHIC CURB & GUTTER	
			AND SIDEWALK	
			NOTES	
			SECTION NUMBER:	100
			DRAWING NUMBER:	W-135B
			DATE:	2/21/2022