

SCOPE OF WORK

1. **WORK UNDER THIS CONTRACT:** includes but is not limited to, all material, labor, tools, expendable equipment, utility and transportation service, any and all travel expenses (previously approved by County), and all incidental items necessary to perform and complete the required Scope of Work in a workmanlike manner, complete and on schedule.

 2. a. The Site Address of the Work to be performed is:

2020-2021 SLURRY SEAL ON SELECTED STREETS IN WASHOE COUNTY

 - b. The Scope of Work includes, but is not limited to, the following. Please refer to attached drawings for complete scope.
 1. Procure all permits and licenses, including, but not limited, to NDOT's temporary encroachment permit and NDEP's Storm Water Discharge Permit, pay all charges, fees and taxes, and give all notices necessary and incidental to the due and lawful prosecution of the work.
 2. Provide all traffic control per Detail Specifications.
 3. All utility covers shall be protected per Detail Specifications.
 4. Sweep & clean all streets to be Micro Sealed and /or Chip Sealed to the satisfaction of the Engineer.
 5. Crack Seal and Patching of selected streets identified in the contract will be responsibility of the contractor. Locations will be identified prior to sealing.
 6. Micro Seal, Chip Seal, and Overlay of the existing paved streets as specified in these specifications, at the locations indicated on the plan description.
 7. Chip Seal emulsion shall meet the special requirements in section 106.02 and have material certifications with bid.
 8. The Contractor shall confirm that the Washoe County Road Department has completed their preparation of the selected streets before submitting a scheduling for approval and coordinate when required for the project.
 9. Provide job cleanup at all sites to the satisfaction of the Engineer.
 10. Work shall be completed within Fifty (50) working days for the Base Bid.
 11. Contractor is responsible to obtain all legal right of entry for any staging areas deemed necessary
 12. A List with locations of all planned staging areas shall be provided at the Pre-Construction meeting.
-